



सुनकोशी गाउँपालिका
गाउँ कार्यपालिकाको कार्यालय

रामटार, सिन्धुली



च.नं. १९६८

२०७३

प.सं. ०८२/०८३



बागमती प्रदेश, नेपाल


मिति: २०८३/०९/०२

जो जससँग सम्बन्धित छ।

विषय :- दररेट पेश गर्ने सम्बन्धमा ।

प्रस्तुत विषयमा सुनकोशी गाउँपालिका योजना शाखाको आ.व. २०८२/०८३ को स्वीकृत वार्षिक कार्यक्रम अन्तरगत वडा नं. ४ को कार्यालय घेराबेराको लागि रु. ९,००,००० र अधुरो विद्यालय भवन सम्पन्न गर्ने तथा विद्यालय भवन मर्मत संभार चिलाउनेखर्क आ.वि. वडा नं ४ को लागि रु. १०,००,००० बजेट विनियोजन भएको हुँदा सूचना प्रकाशन भएको मितिले ७ दिन भित्र (अन्तिम दिन विदा पर्ने भएमा सोको भोलि) सम्म घटाघटमा दररेट पेश गर्न जानकारी गराईन्छ। साथै आशय पत्र पेश गर्दा तपशिल बमोजिमका कागजात पेश गर्न समेत जानकारी गराईन्छ।

१. निर्माण व्यवसायी दर्ता प्रमाणपत्र
२. निर्माण व्यवसायीको इजाजत प्रमाणपत्र
३. स्थायी लेखा नम्बर
४. आ.व. २०८१/२०८२को कर चुक्ता
५. माँग भएको आशय
६. प्रचलित कानून बमोजिमका अन्य कागजातहरू ।


शिवराज पौडेल
प्रमुख प्रशासकीय अधिकृत
शिवराज पौडेल
प्रमुख प्रशासकीय अधिकृत



स्थानीय सरकार
सुनकोशी गाउँपालिका
गाउँ कार्यपालिकाको कार्यालय
रामटार, सिन्धुली
बागमती प्रदेश, नेपाल



म.ले.प.फारम नं: ५०१

कार्यालय कोड नं.: ८०३२५५०६३००

नियमित कार्यको सामत अनुमान ३०९

कार्यक्रम / योजनाको नाम: अधुरो विद्यालय भवन सम्पन्न गर्ने तथा विद्यालय भवन मर्मत संभार चिलाउनेखर्क आ आर्थिक वर्ष: २०८२/८३

कार्यान्वयन हुने स्थल: सु.गा.पा.-०४, सिन्धुली

बजेट: १०,००,०००

क्र. सं.	काम/सेवाको विवरण	इकाई	परिमाण	दर	जम्मा लागत	अनुमानित दरको स्रोत
१	२	३	४	५	६=४x५	७
A	Civil Works					
1	Construction of brick wall using chimney made brick in 1:6 Cement mortar above Ground floor & including 30m transportation (1 Cu.m./35.28 cft)	Cum	8.68			
2	Curtailment, bent up, binding of MS bars according to the drawing for RCC and its transportation upto 30 m	Cum	315.51			
3	1:1½: 3 P.C.C. work in super structure, deck, beam, slab including material collection & transportation up to 30m (for 1 cu.m./ 35.28 cft)	Cum	6.31			
4	12.5 mm thick cement sand (1:6) plaster Cement sand plaster except ceiling	Sq.m	278.83			
5	12.5 mm thick cement sand (1:3) plaster Cement sand plaster on ceiling	Sq.m	232.96			
6	38 mm thick solid pannel local wood shutter (size 1.07m x 1.982m = 2.114 sq.m.)	Sq.m	12.59			
7	38mm thick flush shutter including local wood frame with 4 mm thick teak plywood on both side of shutter	Sq.m	14.25			
8	10*10 mm solid core square rod grill on 4.5*20mm iron plate including panting with red oxide and aluminium paint.	Sq.m	13.19			
9	38 mm thick 1:2:4 plain Cement concrete flooring including cement rubbing	Sq.m	111.60			
B	Electrical works					
10	Light point with 2x1.5 sq. mm. (or 2x3/20) copper cable including HPDE conduit/listi, circular and junction boxes (average length=5.0m)	No.	12.00			
11	Power point with 2x2.5 sq. mm. (or 2x7/22) copper cable including HPDE conduit/listi, circular and junction boxes (average length=5.0m)	No.	8.00			
12	Supply of Concealed type 6" dia. LED light fixture with 10 watt bulb, fixing, testing and comissioning all complete job.	No.	8.00			
13	Supply of 5 pin 15 amp. switch socket, fixing, interconnection ,testing and comissioning all complete.	No.	4.00			
14	Supply, fixing, testing and commissioning of 4 gang one way switch with plate set complete.	No.	4.00			
15	Providing ,fixing inter connection, testing and comissioning of 6-32A DP MCB of IS standard all complete .	No.	4.00			
16	Supply and fixing of 6 Way SPN DB Double Cover	No.	1.00			
				Sub-Total		
				13% VAT		
				Sub-Total with 13% VAT		
				Contingency 4%		
				Total		

शिवराज पौडेल
प्रमुख प्रशासकीय अधिकृत